



STORMWATER DEPARTMENT

City of Mt. Juliet

EROSION CONTROL PERMIT NO: _____

Revised 2/24/06

Applicant		Property Address	
Address		Subdivision/Section	Lot No.
City	State	Impervious Surface/SF	Acres
Project Manager		E-mail	Phone No.
			Fax No.

The following pre-construction and sediment Best Management Practices (BMPs) must be correctly installed prior to the initiation of the disturbance activities:

- A stabilized construction access, such as a temporary stone access, must be installed to prevent offsite tracking.
- Silt fence, or other sediment barrier, must be installed along topographical contours down slope of the area to be disturbed.
- Where applicable, inlet protection for nearby storm sewer curb and drop inlets must be installed.

The following erosion prevention and sediment control BMPs must be performed until the project is completed.

- Non-disturbance easements along streams, rivers and ponds must be provided to avoid erosion of the banks and infiltration of silt.
- Restroom facilities for construction employees must be made available.
- Building and waste materials, and non-storm water discharges, such as concrete or paint wastewater, must be managed to prevent them from entering the storm water system or nearby water body.
- Topsoil should be stripped from all cut and fill areas, stockpiled and redistributed over graded areas to a minimum depth of 6 inches. A sediment barrier must be installed around the base of the stockpile to prevent erosion.
- Stabilization measures must be performed within seven (7) days, or as directed by the Storm Water Coordinator, in portion of the site where construction activities have temporarily or permanently ceased, and within fifteen (15) days of final grading. (Stabilization practices may include: temporary seeding, permanent seeding, mulching, matting and sod stabilization.)
- Inspections of all control measures and disturbed areas must be performed at least once every seventy - two (72) hours. Inspections must be documented and include the date of the inspection and major observations.
- Based on the results of the inspections, any inadequate control measures or control measures in disrepair must be replaced or modified, or repaired as necessary, within seven (7) days after the need is identified.
- Sediment must be removed from sediment barriers and other sediment controls when design capacity has been reduced by 50%.
- Sediment that as escaped the construction site has collected in the street or drainage structures must be physically removed.
- All draining to existing pavement, drainage structures and curbs resulting from new construction must be repaired or replaced by like materials at the builder's expense.
- Septic drain fields, if applicable, must be barricaded and not disturbed.
- All trees designated to remain, must be protected. Heavy equipment should not be operated or stored, nor materials handled or stored within the drip lines of the trees.

I certify that I have reviewed this document and understand the erosion prevention and sediment control requirements herein. I understand that these requirements will be inspected and enforced by the City of Mt. Juliet Public Works Department and failure to comply may result in the issuance of a "stop work order" until compliance is accomplished.

Print Name	Signature	Date
Storm Water Dept. Approval:		Date